

Fencing Overview and Maintenance Strategy

Fencing Overview

Option 1: In accordance with the September 2nd, 2018 Approved Site Plan the Project will install a wire mesh agricultural fence that is approximately 4 feet tall around the perimeter of the project and equipment. There will be a gate at the entrance for access as needed. The fencing consists of wood posts with animal friendly wire mesh, complete with proper signage and security. This fencing will retain low visibility with the proposed plant screening and blend in naturally with the environment.

Option 2: We have also included the option to install a privacy screening mesh along the West, North, and South faces of the Project. This mesh would be removed after the fifth year when the proposed trees have further screened the Project. The privacy screening mesh is colored green to blend in with the natural environment in the best way possible. This option provides additional screening for the first years of the project in areas where the proposed trees gaps may render the project visible during the more barren months.

Option 3: As an alternative, a 7 foot tall wire mesh agricultural fence could be installed with privacy mesh screening similar to option 2 with the plan to remove in the 5th year.

Fencing Maintenance

The proposed wire mesh will be coated with rust resistant finish each year. Accumulated dirt and grass will be removed periodically each year. Fence will be checked for loose parts each year to make sure the integrity of the fence is maintained. Oil on the most vulnerable parts will occur on a regular basis. Replacement for damage parts will be done on an as needed basis. Vegetation along the fence will be mowed periodically. The forest and shrub zones will not be touched unless necessary in order to enhance the screening as much as possible.